BANGALORE DIVISION.

Dated 1st August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 8th September 1930, for Restoring Channasandra Minor Tank register No. 83 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for Restoring Channasandra Minor Tank of Hoskote Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for Restoring Channasandra Register No. 83, Hoskote Taluk, Bangalore District.

No.	Items of work	Unit	Rate	Quantity
	BUND TO R. L. 56·50 AND TOP WIDTH 4'.		Rs.	
1	Cutting grips and clearing jungle	Grade		20
2	Earthwork to bund	C.yds.		6,966
3	Old stone work resetting with new jelly at top course and here and there wherever necessary.	,,		100
4	New stone work	,,		642
5	Turfing	Sq.yds.		5,463
6	Providing new grade stones with numbering and painting.	No.		21
7	Do Index stones	,,		21
8	Do B. M. Stones	,,		2
9	Do Register No. stone	,,		1
10	Do Gauge stone	,,		1
	SLUICE AT R. L. 47·58.			
1	Repairing the existing sluice front and rear cistern and locking arrangements, etc., complete.	Lump	sum	
	WASTE WEIR AT LEFT 80' AND R. L. 52·00.			
1	Dismantling existing masonry steps and retar as at left	Lump	sum	
2	Earthwork	C.yds.		10
3	Burnt brick in surki mortar	C.ft.		636
4	Burnt stone slab dressed new 6" thick	Sq.ft.		45
5	Burnt stone slab old removing and refixing over surki mortar bed.	,,		97
6	Providing bond stones to old and new body wall ...	Lump	sum	
7	Jelly concrete with surki mortar	C.ft.		200
8	Plastering with surki mortar	Sqrs.		7 50
9	New stone work rough	C.yds.		74

Dated 1st August 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 5th September 1930, for Restoring Muthanallur Tank R. No. 213 of Anekal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Muthanallur Tank of Anekal Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities.

Items of work	Per	Rate	Quantity
Bund to R. L. 57·00 and top width 6 feet.		Rs. a. p.	
Clearing jungle grades	Each		23
Cutting grips	C.yds.		839
Earthwork to bund with consolidation	,,		13,508
Turfing	S.yd.		8,535
Lead for earth available from draft cutting and approach clearing from waste weir.	C.yd.		583
New stone work	,,		695
Old stone work with new jelly	,,		200
Providing new grade stones with painting and figuring ...	Each		24
Providing Index stones	,,		34
Providing Reg. No. stone	,,		1
Providing date stone	,,		1
Providing B. M. stones	,,		2
Providing gauge stones	,,		1
Waste weir at left to R. L. 52·00 and 140 feet length.			
Earthwork	C.yd.		584
Burnt brick in surki mortar	C.ft.		650
Burnt stone slabs 6" thick dressed	S.ft.		236
Plastering with surki mortar	Sqr.		9·00
Sluice No. 1 repairs	L. S.		..
Sluice No. 2 construction as per type design	L. S.		..

N. G. KRISHNA IYENGAR,
Executive Engineer.